KOLAR DIVISION.

Notice dated 29th July 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M., 28th August 1930, for Restoring Volagamadi Royarkere Regd., No. 593 of Bowringpet Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1931.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees two hundred and forty in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Restoring Volagamadi Royarkere Regd. No. 593 of Bowringpet Taluk in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders, will be returned.

9. The tenderer must quote specific rates for all items both in words and in figures.

10. The tender stating that the work would be executed at a certain percentage in excess of or lower than the estimate will not be accepted.

Abstract estimate for Restoring Dodda Volagamadi Royarkere Register No. 593 of Bowringpet Taluk.

No.	Items of work	Unit	Rate	Quantity	Cost
	BUND.		Rs. a. p.		
1	Earthwork to bund with watering and tamping, bed soil.	C.yd.		5,061	
2	Gravelly soil to be used for the existing bund with watering and tamping including bed.	,,		1,522	
3	Turfing	S.yd.		3,846	
4	Removing and resetting old stone revetment with new jelly.	C.yd.		758	
5	New stone work	,,		188	
6	Providing grade stones with forming painting, etc., complete.	No.		15	
6a	INDEX STONES.	,,		15	
7	Do B. M. stones	,,		2	
8	Providing Regd. No. date stone	,,		1	
9	Providing jungle stone	,,		1	
10	Clearing jungle over the existing bund including cutting grips over top of bund.	Grade		10	
11	Preparing seats of bund between C. S. O. & 1 A and up to end.	Lump sum		...	

No.	Items of work	Unit	Rate	Quantity	Cost
	SLUICE AT R. L. 50·00.		Rs. a. p.		
1	Earthwork cutting	C.yd.		89	
2	Concrete in surki mortar	C.ft.		119	
3	Burnt brick in surki mortar	„		321	
4	Burnt stone slabs 6" thick	S.ft.		196	
5	Boring holes in orifice slabs	No.		3	
6	Plastering with surki mortar	Sqr.		5·46	
7	Providing plug and rod	Lump sum		...	
8	Refilling the cut with watering and tamping ...	C.yd.		36	
	WASTE WEIR 90' LONG AT R. L. 55·00.				
1	Earthwork excavating and using the same to flank bund with watering and tamping.	C.yd.		325	
2	Excavation in rock	„		9	
3	Concrete in surki mortar	C.ft.		251	
4	Burnt brick in surki mortar	„		2,337	
5	Burnt stone slabs 6" thick	S.ft.		317	
6	Plastering with mortar	S.qrs.		19·42	
7	Rough stone work new	C.ft.		153	
8	Jelly filling below apron	„		117	
9	Providing peir slabs 3'×1'	No.		10	
10	Providing joggle joints	„		15	
	Total ...	...	...	...	...
	Total bund, sluice and weir ...	...	...	...	...
	Contingencies ...	...	...	...	...
	Grand Total ...	...	...	...	...

N. LAKSHMINARASIMHIAYA,
Executive Engineer.

THE BANK OF MYSORE, LIMITED, BANGALORE.

Statement of the affairs of the Bank of Mysore, Limited, for the week ending 31st July 1930, published under Article 141 of the Articles of Association.

LIABILITIES		Rs.	ASSETS		Rs.
To Capital Receipts	...	20,00,000	By Cash in Hand and at Bankers		17,99,490
Reserve Funds	...	18,00,000	„ Loans & Cash Credit Accounts		1,81,54,734
Public and other Deposits	..	1,99,22,826	„ Bills discounted	...	4,67,317
„ Sundries	..	2,07,359	„ Investments	...	18,34,717
			„ Balance at Agencies	...	16,082
(Annas and pies omitted.)			„ Dead Stock	...	5,74,162
			„ Sundries	..	83,683
Total	... Rs.	2,39,30,185	Total	.. Rs.	2,39,30,185

BANGALORE,
Dated 5th August 1930.

P. W. O'BRIEN,
Manager.